



VIDYASAGAR COLLEGE

NAAC ACCREDITED

39, SANKAR GHOSH LANE, KOLKATA-700 006

PHONE : (Principal) - 2241-3018,

(Office) : 2241-4447

Website : www.vidyasagarcollege.edu.in

E-mail : vidyasagarcollegekolkata@gmail.com

Ref. No. VC/T/SC/10/16

Date : 08/06/2016

Tenders requested for the following 2 items

① a. Quotation No. 1.

Name of work :- Electrical installation for Computers at Library and Security lighting at College Campus of Vidyasagar College. Plot no - CL-3-8, 44 to 50 Sector II, Salt Lake, Kolkata.

Sl. No	Description of work	Qty	Unit
1	Distribution wiring in 3x3/0.36 PVC insulated and sheathed copper wire in 1/2" width and 1/8" thick casing complete with all accessories embedded in wall to 4 no plug point 15A with piano type switch on lexanelite sheet with top cover 3mm thick flashed in wall mending good damage to original finish average run - 10 mtr.	2 NOS	m
2	Distribution wiring in 3x3/0.36 P.V.C insulated and sheathed copper wire in 1/2" width and 1/8" thick casing complete with all accessories embedded in wall to light point	220	mtr.
3	Supply and fixing projected lamp bracket made of 50 mm dia G.I. pipe of 6' ft length of which 3' ft in projection having an angle 105° with clamps bolts, nuts etc. as required.	4	nos.
4	Supply and fixing of lighting luminaries 230 Volt complete with all accessories. 1x70 watt CDMTT 70W with 1x70W CDMTT lamp	4	nos.



Gulshan 2/1
8/6/16
Principal
Vidyasagar College
Calcutta-700006



VIDYASAGAR COLLEGE

NAAC ACCREDITED

39, SANKAR GHOSH LANE, KOLKATA-700 006

PHONE : (Principal) - 2241-3018,

(Office) : 2241-4447

Website : www.vidyasagarcollege.edu.in

E-mail : vidyasagarcollegekolkata@gmail.com

Ref. No. VC/T/SL/11/16

Date : 06.06.2016

Quotation No. 2
Name of work :- Remodelling, repairing and replastering of College building for Vidyasagar College at Plot No - C-3 to 8 and 44 to 50 Sector II, Salt Lake Kolkata.

SL No	Description of works	Qty	Unit
1.	Breaking, rubbing, cleaning and removing of old damage plaster inside the building and treating with one coat of Sika Latex and replastering upto 20 mm. - 500	500	sqft
2.	Temporary construction of shed over the lift duct and covering stair cases with necessary M.S. pipe and P.V.C sheet complete - 250	250	sqft
3.	Repairing the collapsible gate with necessary cutting and welding by replacing with nails, runners and channels and making good damages complete 10	10	sqft
4.	Supply and fixing M.S. ornamental grill of approved design joint continuously welded with M.S. flats and bars for windows, fitted and fixed with necessary screws and legs 5	5	sqft
5.	Supply and fixing of door closer and Catcher. 20	20	no
6.	Dismantling the part of the existing urinal and construction of new W.C. of approved size with glazed tiles on wall and floor and fixing the Comode with Cystem 1	1	Item

Quotations to be dropped in the drop box placed at 39, Sankar Ghosh Lane, Kolkata-6 from 12.00 noon to 5.00 pm.

Last Date of quotation receiving : 15th June, 2016 at 3.30 pm.

Opening of tender : 15th June at 4.30 pm.



Gent an me
8/6/16
Principal
Vidyasagar College
Calcutta-700006