



VIDYASAGAR COLLEGE

NAAC ACCREDITED

39, SANKAR GHOSH LANE, KOLKATA-700 006

PHONE: (Principal) - 2241-3018,

(Office) : 2241-4447

Name of work: Construction of boundary wall at the entrance gate
 Website: www.vidyasagarcollege.edu.in E-mail: vidyasagarcollegekolkata@gmail.com
 Ref. No. Of Hostel Building, Vidyasagar College, Bidhan Sar

Sl. No	Description	Qty.
1.	Earth work in excavation of foundation trenches in all shots of soil including ramming, spreading, or hauling the spoils within a lead of 3" as directed. The item includes necessary trimming the side of trenches, levelling, dressing and removing bottom bailing out water etc. as required complete -	100 cft.
2.	Single brick flat Soling (3") with pierced jhama bricks	50 sqft.
3.	25 mm thick damp proof course with stone chips (4:2:1) double chequered complete with water proofing compound as per manufacturer specification -	50 sqft.
4.	Brick work in Cement mortar (6:1) a) In foundation plinth - b) In ground floor	100 cft. 200 cft.
5.	Plaster to wall with sand and cement mortar including rounding off or chamfering corners as directed and racking out joints or roughening of concrete surface including pointing, nosing & drip course where necessary - In ground floor 12 mm thick (1:6)	400 sqft.
6.	White washing including cleaning and smoothing surface thoroughly	400 sqft.
7.	Dismantling and re-fixing of existing M.S grill gate of size 5'-0" x 6'-0" with necessary clamps, nuts, bolts etc as required	2 sets.

BY ORDER

Last Date: 3RD OCT '2016 at 4:00pm.